

## **Standard Operating Procedure:**

### **Workplace Safety Compliance & Incident Management**

**Document Code:** SOP-CO-003

**Version:** 1.7

**Effective Date:** 25 January 2024

**Last Updated:** 5 February 2025

**Published by:** Infrastructure Development Department

**Related Policy:** POL-CO-003 Occupational Health, Safety & Security Policy

## **1. PURPOSE AND SCOPE**

This SOP operationalizes POL-CO-003 safety requirements through daily compliance procedures, permit-to-work systems, inspection protocols, and structured incident management workflows.

## **2. PRE-WORK SAFETY BRIEFING PROCEDURES**

### **2.1 Daily Toolbox Talks (Mandatory)**

**Timing:** Every workday within 30 minutes of shift start

**Duration:** Minimum 15 minutes per POL-CO-003 contractor obligations

**Led by:** Contractor's Site Supervisor (or equivalent) or competent foreman

**Attendance:** Mandatory for all workers performing tasks that day (documented on Document TT-75)

#### **Toolbox Talk Content:**

- Day's work scope and sequence
- Specific hazards for planned activities
- Control measures and safe work procedures
- PPE requirements per POL-CO-003 Section 3.2 hierarchy

- Permit-to-work requirements (if applicable)
- Emergency procedures and muster points
- Previous day's incidents/near-misses and lessons learned
- Stop-work authority reminder

The Contractor's Site Supervisor (or equivalent) shall record attendance for every toolbox talk, including worker signatures, topics covered, and questions raised, and failure to attend without a valid reason shall result in disciplinary action.

## **2.2 Task-Specific Briefings**

For high-risk activities (confined space, working at height >3m, hot work, lifting operations):

- Conduct an additional task-specific briefing by the Contractor's Safety Officer (or equivalent) prior to commencement of work.
- Review the relevant task-specific risk assessment in accordance with POL-CO-003 Section 3.1.
- Confirm that all personnel have valid specialized training as required under POL-CO-003 Section 4.2.
- Verify that appropriate emergency rescue arrangements are in place before work begins.

## **3. PERMIT-TO-WORK SYSTEM**

### **3.1 Permit Categories and Approval Authorities**

#### **Document PTW-CS-80: Confined Space Entry**

- **Definition:** A space not designed for continuous occupancy, with limited means of entry or exit, and potential atmospheric or other hazardous conditions.
- **Examples:** Tanks, manholes, sewers, tunnels, and pits exceeding 1.2 meters in depth.
- **Approval authority:** HCSA HSE Department

- **Additional requirements:** Atmospheric testing prior to entry and at regular intervals, assignment of a standby person, provision of appropriate rescue equipment, and an effective communication system.
- **Validity:** This permit is valid for eight (8) hours only. A new permit must be obtained if work continues beyond this period.

#### **Document PTW-HW-82: Hot Work**

- **Definition:** Work that produces sparks, open flames, or heat exceeding 100°C, including but not limited to welding, cutting, grinding, and brazing.
- **Approval authority:** HCSA HSE Department
- **Additional requirements:** Deployment of designated fire watch personnel, availability of appropriate firefighting equipment, clearance of flammable materials within a 10-meter radius, and maintenance of a post-work fire watch for a minimum of 60 minutes after completion of work.
- **Validity:** This permit is valid for twenty-four (24) hours only. A new permit must be obtained if work continues beyond this period.

#### **Document PTW-WAH-84: Working at Height**

- **Definition:** Work conducted at heights exceeding 3 meters above ground level or above a dangerous surface, including water, operating machinery, or hazardous chemicals.
- **Approval authority:** HCSA HSE Department
- **Additional requirements:** Implementation of appropriate fall protection systems, an established and documented rescue plan, and continuous weather monitoring, with work suspended when wind speeds exceed 40 km/h.
- **Validity:** This permit is valid for seven (7) calendar days only. A new permit must be obtained if work continues beyond this period.

#### **Document PTW-LO-86: Lifting Operations**

- **Definition:** The use of cranes, hoists, or other lifting equipment for handling loads exceeding one (1) tonne.

- **Approval authority:** HCSA HSE Department
- **Additional requirements:** Preparation and approval of a lift plan, establishment of a clearly demarcated exclusion zone, assignment of a qualified signaller, and verification of valid load certification.
- **Validity:** This permit is valid for seven (7) calendar days only. A new permit must be obtained if work continues beyond this period.

### 3.2 Permit Issuance Process

1. Workers or Supervisors shall submit permit applications at least one (1) working day prior to the scheduled commencement of work for general work permits, and at least two (2) working days prior to the scheduled commencement of work for Confined Space Entry Permits. No work shall proceed under an expired permit. Where a permit has expired, a new application shall be submitted and approved within the stipulated timeframes before work resumes.
2. The relevant Risk Assessment Document RA-55 shall be completed and approved in accordance with POL-CO-003 Section 3.1 prior to permit issuance.
3. The Contractor's Safety Officer (or equivalent) shall conduct a site inspection to verify that all required control measures are in place and effective.
4. The designated approval authority shall review the permit application and sign the permit.
5. The approved permit shall be displayed prominently at the work location, and a copy shall be retained by the Contractor's Safety Officer (or equivalent).
6. A pre-work briefing shall be conducted to communicate the permit conditions, associated hazards, and required control measures to all affected personnel.
7. The permit shall be formally closed upon completion of the work or at the end of the shift, whichever occurs earlier.

### 3.3 Permit Suspension and Cancellation

- Work shall be immediately stopped if site conditions change, including but not limited to adverse weather, conflicting adjacent activities, equipment failure, or any circumstance that affects the effectiveness of the approved control measures.

- The permit may be suspended by the Contractor's Safety Officer (or equivalent) or by any person exercising stop-work authority in accordance with POL-CO-003 Section 1.3.
- Work shall not resume until the identified issues have been resolved, control measures have been reassessed, and the permit has been revalidated by the original approval authority.

## 4. DAILY SAFETY INSPECTION CHECKLISTS

### 4.1 Document DSI-CS-90: Construction Site Inspection

- **Conducted by:** Contractor's Safety Officer (or equivalent) daily before work commencement (7:00 AM standard)
- **Focus areas:** Housekeeping: Ensure walkways are clear of obstructions, materials are stacked and secured safely, and waste is properly segregated and disposed of.
- **Scaffolding:** Check the presence and condition of toe boards, guardrails, and bracing, and confirm platform integrity, with a comprehensive inspection conducted at least once weekly.
- **Electrical Safety:** Ensure GFCI protection is provided where required, electrical cables are in good condition, temporary lighting is adequate and safe, and lockout/tagout procedures are properly implemented.
- **Excavations:** Ensure appropriate shoring or support systems are installed, barricades are in place, safe access via ladders is provided, and no hazardous water accumulation is present.
- **Machinery:** Ensure machine guards and emergency stop functions are operational and operator certifications are valid and visibly displayed.
- **PPE Compliance:** Conduct spot-checks on a minimum of ten (10) percent of the workforce to ensure the proper use of required personal protective equipment.
- **Fire Prevention:** Ensure fire extinguishers are properly positioned and accessible, fire watch requirements are complied with, and flammable materials are stored safely in designated areas.

## **4.2 Document DSI-OB-92: Office/Building Inspection**

**Conducted by:** Facility Contractor's Supervisor (or equivalent) weekly

- **Emergency Exits:** Ensure all emergency exits are unobstructed and that exit signage is clearly visible and illuminated.
- **Fire Extinguishers:** Ensure fire extinguishers are properly serviced, with annual inspection tags valid and up to date.
- **First Aid Kits:** Ensure first aid kits are fully stocked, clearly identified, and readily accessible.
- **Ergonomic Workstations:** Ensure workstations comply with Display Screen Equipment (DSE) assessment requirements and ergonomic standards.
- **Slip and Trip Hazards:** Ensure floors are free from slip and trip hazards, including loose cables, wet surfaces, and uneven flooring.
- **Security Systems:** Ensure security systems, including access control, CCTV, and alarm systems, are operational and functioning as intended.

## **4.3 Non-Compliance Response**

- **Critical safety violations:** Immediate work stoppage shall be enforced, and the Contractor's HSE Manager (or equivalent) shall be notified within fifteen (15) minutes.
- **Major violations:** Corrective action shall be implemented within four (4) hours and formally documented.
- **Minor violations:** Corrective action shall be implemented within twenty-four (24) hours.

## **5. INCIDENT NOTIFICATION WORKFLOW**

### **5.1 Immediate Response (First 15 Minutes)**

**Any person discovering incident:**

1. Ensure the scene is safe, render first aid if trained and competent to do so, and contact emergency services where required.

2. Notify the Contractor's Site Supervisor (or equivalent) immediately upon discovery of the incident.
3. Preserve the incident scene by establishing barricades where necessary, taking photographs, and preventing unauthorized disturbance of evidence.

**Contractor's Site Supervisor (or equivalent) actions within 15 minutes:**

1. Assess the incident severity in accordance with the classification definitions set out in POL-CO-003 Section 5.1.
2. Where the incident is borderline between Level 2 and Level 3 and involves potential for serious injury, immediately escalate the matter to the Contractor's HSE Manager (or equivalent) in accordance with POL-CO-003 Section 5.2.
3. Initiate the required verbal notifications based on the confirmed or preliminary severity level.
4. Complete the preliminary Incident Notification Document INF-95 and submit it to the Contractor's HSE Manager (or equivalent) without delay.

**5.2 Notification Timelines by Severity (per POL-CO-003 Section 5.3)**

**Level 1 incidents:**

- Verbal notification shall follow the escalation chain within 15 minutes: Contractor's Site Supervisor (or equivalent) → Contractor's Project Manager (or equivalent) → Contractor's HSE Manager (or equivalent) → Contractor's HSE Director (or equivalent) → Contractor's Deputy CEO (or equivalent).
- The Contractor's HSE Director (or equivalent) shall formally notify HCSA's HSE Department within one (1) day of the incident.
- A written incident report using Document IR-62 shall be submitted within eight (8) hours of the incident.

**Level 2 incidents:**

- Verbal notification shall follow the escalation chain within 15 minutes: Contractor's Site Supervisor (or equivalent) → Contractor's Project Manager (or equivalent) →

Contractor's HSE Manager (or equivalent) → Contractor's HSE Director (or equivalent).

- The Contractor's HSE Manager (or equivalent) shall notify the Contractor's HSE Director (or equivalent) within one (1) hour of the incident.
- If the incident involves a borderline classification, the Contractor's HSE Manager (or equivalent) shall conduct a rapid assessment within one (1) hour and issue the final classification using Document IC-65.
- A written incident report using Document IR-62 shall be submitted within twelve (12) hours of the incident.
- HCSA's HSE Department shall be formally notified within seven (7) calendar days in the case of dangerous occurrences.

#### **Level 3 incidents:**

- Verbal notification shall follow the escalation chain within 1 hour: Contractor's Site Supervisor (or equivalent) → Contractor's Project Manager (or equivalent) → Contractor's HSE Manager (or equivalent).
- A written incident report using Document IR-62 shall be submitted within twenty-four (24) hours of the incident.
- HCSA's HSE Department shall be formally notified within seven (7) calendar days.

#### **Level 4-5 incidents:**

- The incident shall be recorded in the Daily Safety Log using Document DSL-97 on the same day of occurrence.
- A consolidated weekly report shall be submitted to the Contractor's HSE Manager (or equivalent).
- HCSA's HSE Department shall be formally notified within seven (7) calendar days.

### **5.3 Borderline Incident Classification Process**

**When the Contractor's Site Supervisor (or equivalent) is uncertain between Level 2 and Level 3:**

**Step 1: Immediate containment (0-15 minutes)**



- Secure the incident scene and provide appropriate medical response as required.
- Make a preliminary classification based on the actual outcome of the incident in accordance with POL-CO-003 Section 5.1.
- Escalate the incident for review by the Contractor's Project Manager (or equivalent) and Contractor's HSE Manager (or equivalent) where indicators of potential for serious injury are present, including but not limited to:
  - Falls from height exceeding two (2) meters, regardless of injury severity;
  - Struck-by or caught-between incidents involving heavy equipment or vehicles;
  - Electrical contact at any voltage;
  - Chemical exposure involving substances with health hazard warnings in the applicable Safety Data Sheet (SDS);
  - Structural failure or partial or total collapse;
  - Any incident occurring within a confined space.

**Step 2: Contractor's Project Manager (or equivalent) and Contractor's HSE Manager (or equivalent) rapid assessment (15-60 minutes)**

- Conduct interviews with the injured person and relevant witnesses to establish the sequence of events.
- Evaluate the energy level involved and the potential consequences in accordance with POL-CO-003 Section 5.2.
- Consider if slightly different circumstances could reasonably have resulted in a Level 2 classification.
- Review similar incidents within industry databases or internal records to determine typical consequences.
- Issue the preliminary classification using Document IC-65.

**Step 3: Final classification confirmation (1-4 hours)**

- Obtain the medical assessment report, where available, to support the classification decision.

- Consult the Contractor's HSE Director (or equivalent) if a Level 1 or Level 2 classification is likely.
- Issue the final classification determination and initiate the appropriate investigation in accordance with Section 6.

#### **Example application:**

- A worker slips on a wet floor, falls backward, strikes his head against a wall, reports dizziness, and is sent to the hospital for observation for four (4) hours; he is diagnosed with a minor concussion and released on the same day.
- **Initial classification:** Level 3, as hospitalization was less than twenty-four (24) hours.
- **Borderline consideration:** Head injury with potential for loss of consciousness presents a risk of serious injury.
- The Contractor's HSE Manager (or equivalent) reviews CCTV footage confirming no loss of consciousness and considers the medical report confirming a minor concussion with no ongoing symptoms.
- **Final classification:** Level 3 confirmed and not escalated to Level 2.
- If the worker had experienced loss of consciousness exceeding five (5) minutes, the incident would have been escalated to Level 2.

## **6. INVESTIGATION METHODOLOGY**

### **6.1 Investigation Method Selection (per POL-CO-003 Section 6.2)**

#### **Document 5W-68 5-Whys Method:**

- **Use for:** Applicable to Level 4 and Level 5 incidents involving simple and linear causation.
- **Example:** A worker cuts a hand on a sharp edge. Why? The guard was missing. Why? Maintenance was not performed. Why? There was no maintenance schedule. Why? The equipment was not registered in the CMMS. Root cause: Asset management gap.
- **Timeline:** The investigation shall be completed within three (3) business days.

- **Led by:** The Contractor's Site Supervisor (or equivalent), with support from the Contractor's Safety Officer (or equivalent).
- **Review:** The investigation findings shall be submitted to the Contractor's HSE Manager (or equivalent) for review and approval prior to closure.

#### **Document RCA-70: Root Cause Analysis - RCA:**

- **Use for:** Applicable to Level 1 to Level 3 incidents involving multiple contributing factors, systemic weaknesses, or complex human and organizational factors.
- **Methodology:**
  - Conduct timeline reconstruction supported by witness interviews and evidence review.
  - Develop a fishbone diagram covering categories such as people, process, equipment, environment, and management.
  - Identify immediate causes (unsafe acts or conditions), followed by basic causes (personal or job factors), and ultimately root causes (organizational or systemic failures).
  - Apply the 5-Whys technique to each contributing factor branch to validate root cause determination.
- **Timeline:**
  - Level 1–2 incidents: Investigation to be completed within ten (10) business days.
  - Level 3 incidents: Investigation to be completed within seven (7) business days.
- **Led by:**
  - Level 1–2 incidents: The Contractor's HSE Director (or equivalent), with engagement of an external specialist where required.
  - Level 3 incidents: The Contractor's Project Manager (or equivalent), Contractor's HSE Manager (or equivalent), Contractor's Site Supervisor (or equivalent), and Contractor's Safety Officer (or equivalent).

- **Review:** Investigation findings shall be reviewed and approved by the Contractor's HSE Director (or equivalent), with a formal briefing provided to the CEO in the case of Level 1 incidents.

## **6.2 Investigation Process**

1. Preserve all relevant evidence within twenty-four (24) hours, including photographs, physical evidence, and witness statements.
2. Reconstruct the sequence of events and establish a clear timeline of the incident.
3. Identify all contributing factors and avoid limiting the analysis to the first apparent cause.
4. Apply the appropriate investigation methodology, either the 5-Whys technique or Root Cause Analysis (RCA), as required.
5. Determine the root causes, focusing on organizational and systemic factors rather than individual blame.
6. Develop corrective actions in accordance with the control hierarchy set out in POL-CO-003 Section 3.2.
7. Document the investigation findings in a formal investigation report and record all corrective actions in the action register.
8. Present the investigation findings to the Contractor's Project Manager (or equivalent) and the Contractor's HSE Director (or equivalent).

## **7. CORRECTIVE ACTION TRACKING**

### **7.1 Document CAR-100: Action Register**

- All corrective actions logged with:
- Description of the corrective action and designation of the responsible person.
- Target completion date determined based on the level of urgency and risk.
- Identification of required resources and associated budget allocation.
- Defined method of verification to confirm effective implementation.
- Designated authority responsible for review and formal closure sign-off.

## **7.2 Closure Timelines by Incident Severity**

### **Level 1-2 incidents:**

- Critical actions: To be implemented within a maximum of seven (7) calendar days.
- Major actions: To be implemented within a maximum of thirty (30) calendar days.
- System improvements: To be implemented within ninety (90) calendar days, with clearly defined interim milestones and progress monitoring.

### **Level 3 incidents:**

- Critical actions: To be implemented within fourteen (14) calendar days.
- Other actions: To be implemented within sixty (60) calendar days.

### **Level 4-5 incidents:**

All corrective actions shall be implemented within thirty (30) calendar days.

## **7.3 Verification and Closure**

- The Contractor's Safety Officer (or equivalent) shall confirm on-site implementation of corrective actions.
- Photographic evidence shall be obtained for physical control measures implemented.
- Training records shall be updated and retained where corrective actions involve procedural changes.
- The Contractor's HSE Manager (or equivalent) shall provide final review and closure approval.
- Any overdue actions shall be escalated on a weekly basis to the Contractor's HSE Director (or equivalent).

## **8. SAFETY PERFORMANCE REPORTING**

### **8.1 Weekly Site Report (Contractor's Safety Officer (or equivalent) to Contractor's HSE Manager (or equivalent))**

- Toolbox talk completion rate, including attendance statistics and any missed sessions.

- Summary of permit-to-work issuance, compliance status, and any permit violations identified.
- Findings from daily safety inspections and the status of corrective actions.
- Summary of Level 4–5 incidents recorded during the reporting period.
- Details of safety training conducted, including number of participants and training hours delivered.
- Record of non-compliance observations and actions taken to address them.

## **8.2 Monthly Safety Report (Contractor's HSE Manager (or equivalent) to Contractor's HSE Director (or equivalent) and Contractor's Project Manager (or equivalent))**

### **KPIs reported:**

- Lost Time Injury Frequency Rate (LTIFR): Target of less than 1.0 per 1,000,000 man-hours worked.
- Total Recordable Injury Rate (TRIR): Target of less than 3.0 per 1,000,000 man-hours worked.
- Near-Miss Reporting Rate: Target of more than ten (10) near-miss reports per month as a leading safety performance indicator.
- Safety Training Hours per Worker: Target to meet or exceed the minimum annual training hours specified in POL-CO-003 Section 4.1.
- Inspection Completion Rate: Target of 100% completion of scheduled inspections.
- Corrective Action Closure Rate: Target of more than 90% of corrective actions closed within the stipulated timeframe.

## **8.3 Quarterly Safety Review (Contractor's HSE Director (or equivalent))**

- Analysis of portfolio-wide safety performance trends, including key indicators and emerging risk patterns.
- Summary of major incidents (Level 1–3), including root causes, corrective actions, and lessons learned.
- Evaluation of Contractor safety performance, including compliance scores and performance ratings.

- Summary of audit findings and overall compliance status with statutory and HCSA requirements.
- Updates on relevant regulatory changes and assessment of their impact on existing policies and operations.
- Assessment of safety culture, including leadership engagement, worker participation, and reporting behaviors.

## **9. INTEGRATION WITH OTHER POLICIES**

- **POL-IS-003 Asset Management:** Handover safety documentation, defect response for safety-critical assets
- **POL-UD-001 Development Approval:** EIA requirements include occupational health impacts
- **POL-UD-002 Sustainability:** Indoor environmental quality standards align with health requirements

### **Document Control:**

*Last Updated: 5 February 2025*

*Change Log: Version 1.7 - Enhanced borderline incident classification workflow*