

Standard Operating Procedure:

Sustainability Assessment & Certification Process

Document Code: SOP-UD-002

Version: 2.4

Effective Date: 15 January 2025

Review Date: 15 January 2026

Owner: Sustainability and Environment Department

Related Policy: POL-UD-002 Green Building & Sustainability Standards Policy

1. PURPOSE AND SCOPE

1.1 Purpose

This SOP establishes the standardized process for conducting sustainability assessments, pursuing green building certifications, and monitoring sustainability performance throughout project lifecycle, ensuring compliance with POL-UD-002.

1.2 Scope

Applies to:

- All projects subject to mandatory certification requirements per POL-UD-002 Section 5.1
- Voluntary sustainability assessments for projects below certification thresholds
- Post-occupancy sustainability performance monitoring
- Exception request processing for sustainability deviations

1.3 Process Owner

The Contractor's Assistant Project Director (or equivalent) maintains overall accountability, with the Sustainability Consultant providing specialised technical execution.

2. ROLES AND RESPONSIBILITIES

2.1 HCSA's Project Manager

- Strategic sustainability oversight and budget allocation
- Sustainability consultant procurement and management
- Conflict resolution between sustainability and project constraints
- Exception request initiation per POL-UD-002 Section 8
- Final sign-off on sustainability strategy and certification submissions

2.2 Sustainability Consultant (External Accredited)

- Technical sustainability assessments and scoring calculations
- Green building certification coordination and submissions
- Design optimization recommendations
- Monthly sustainability performance reporting
- Third-party verification coordination
- Preparation of all sustainability documentation and forms

2.3 Contractor's Lead Architect (or equivalent)

- Design integration of sustainability features
- Material selection aligned with POL-UD-002 Section 2.4
- Collaboration with Sustainability Consultant on design optimization
- Preparation of sustainability-related design drawings and specifications
- Value engineering participation for sustainability features

2.4 Contractor's Project Manager (or equivalent)

- Sustainability milestone tracking and schedule integration
- Coordination of sustainability workshops and reviews
- Documentation management in project repository
- Liaison between Sustainability Consultant and delivery team
- Monthly reporting compilation

3. SUSTAINABILITY CONSULTANT PROCUREMENT

3.1 Consultant Qualification Requirements

Mandatory qualifications:

- Accredited Professional status in relevant certification scheme (LEED AP, BREEAM Assessor, or equivalent)
- Minimum 5 years' experience
- Portfolio of minimum 10 certified projects in similar building typology
- Professional indemnity insurance: minimum \$2M coverage
- Firm must hold ISO 14001 Environmental Management System certification

Evaluation criteria (100 points total):

- Technical qualifications and certifications: 30 points
- Relevant project experience: 25 points
- Proposed methodology and approach: 20 points
- Team composition and capacity: 15 points
- Fee proposal (value for money): 10 points

3.2 Procurement Process

1. Issue Request for Proposals (RFP) to minimum 3 qualified firms
2. Evaluation by panel: HCSA's Development Projects Deputy Director, HCSA's Development Projects Director, Sustainability and Environment Director
3. Shortlist top 3 firms for interview presentations
4. Reference checks with minimum 3 previous clients
5. Appointment recommendation to DCEO(B)
6. Contract execution within 10 business days of approval

Standard appointment timing: Within 2 weeks of project initiation, before concept design commencement.

4. PRE-DESIGN SUSTAINABILITY WORKSHOP

4.1 Workshop Timing and Participants

Timing: Within 3 weeks of project initiation, before schematic design begins

Mandatory participants:

- HCSA's Project Manager
- Contractor's Lead Architect (or equivalent) and Contractor's design team leads (structural, M&E, and landscape) (or equivalent)
- Contractor's Sustainability Consultant (or equivalent)
- Contractor's Cost Consultant / Quantity Surveyor (or equivalent)
- Contractor's Project Manager (or equivalent)
- Contractor's Compliance Officer (or equivalent)

4.2 Workshop Agenda and Objectives

Duration: Full day (8 hours minimum)

Session 1: Policy Framework Review (90 minutes)

- Review POL-UD-002 mandatory and aspirational targets
- Confirm project-specific sustainability objectives and certification target
- Identify applicable thresholds: project value tier, renewable energy requirements, certification level
- Review statutory sustainability requirements beyond company policy

Session 2: Site and Context Analysis (120 minutes)

- Review site constraints and opportunities
- Climate analysis and passive design strategies
- Biodiversity assessment requirements per POL-UD-002 Section 4
- Infrastructure and utility availability
- Identify potential sustainability risks and opportunities

Session 3: Sustainability Strategy Development (180 minutes)

- Energy efficiency approach and renewable energy strategy
- Water conservation and management approach
- Material selection strategy per POL-UD-002 Section 2.4
- Indoor environmental quality priorities
- Biodiversity preservation and enhancement measures
- Innovation opportunities and aspirational targets

Session 4: Certification Pathway and Scoring (90 minutes)

- Preliminary certification scorecard completion (100-point scale)
- Identify "low-hanging fruit" credits and challenging requirements
- Budget allocation for sustainability features (preliminary)
- Risk assessment: likelihood of achieving target certification level
- Contingency planning: credits to pursue above minimum for buffer

Session 5: Integration and Action Planning (60 minutes)

- Sustainability milestone integration with project schedule
- Assign responsibilities for sustainability deliverables
- Establish monthly reporting protocol
- Document sustainability strategy in Workshop Report Form WR-09

4.3 Workshop Deliverables

- Sustainability Strategy Document (20-30 pages)
- Preliminary certification scorecard with target points per category
- Sustainability features budget estimate
- Risk register for sustainability compliance
- Action plan with assigned responsibilities and deadlines
- Completed Workshop Report Form WR-09

Approval: HCSA's Project Manager approval required within 5 business days. Workshop outputs incorporated into Project Charter.

5. SUSTAINABILITY ASSESSMENT SCORING METHODOLOGY

5.1 100-Point Scoring Framework

Point allocation across categories:

- Energy Performance: 30 points maximum
- Water Efficiency: 15 points maximum
- Materials and Resources: 15 points maximum
- Indoor Environmental Quality: 15 points maximum
- Innovation and Design Process: 10 points maximum
- Site Sustainability and Biodiversity: 15 points maximum

Certification levels:

- Certified: 50-59 points (minimum for projects \$15M-\$30M per POL-UD-002 Section 5.1)
- Silver: 60-74 points (minimum for projects \$30M-\$75M)
- Gold: 75-89 points (minimum for projects >\$75M)
- Platinum: 90-100 points (aspirational leadership level)

5.2 Energy Performance Scoring (30 points maximum)

Baseline: Local building code compliance = 0 points

Improvement tiers:

- 15-20% improvement over baseline: 10 points
- 21-30% improvement: 18 points
- 31-40% improvement: 25 points
- 40% improvement: 30 points

Renewable energy provisions (integrated into energy scoring):

- **For projects <\$10M:** 15% renewable energy = 3 bonus points within energy category

- **For commercial projects >5,000 sqm GFA (all values):** 20% renewable energy = mandatory minimum per POL-UD-002 Section 2.2 (no bonus points, failure to meet results in non-compliance)
- Additional renewable energy beyond mandatory minimum: +1 point per 5% increment (max 5 bonus points)

Note: The 15% threshold for projects <\$10M creates a compliance pathway that differs from POL-UD-002 Section 2.2 which states 20% for all commercial projects >5,000 sqm. Projects must meet the higher threshold when both conditions apply (commercial >5,000 sqm AND any project value tier). Sustainability Consultant must flag any discrepancy to Contractor's Assistant Project Director (or equivalent) for clarification and document in Assessment Report.

5.3 Water Efficiency Scoring (15 points maximum)

- 15-20% reduction vs. baseline: 6 points (mandatory minimum per POL-UD-002 Section 2.3)
- 21-30% reduction: 10 points
- 30% reduction: 15 points
- Rainwater harvesting for 50%+ irrigation: included in mandatory baseline
- Greywater recycling (for projects >10,000 sqm): +2 bonus points if exceeding mandatory requirement

5.4 Materials and Resources Scoring (15 points maximum)

Mandatory minimums per POL-UD-002 Section 2.4 (required for any points):

- Concrete: 15% recycled content
- Steel: 30% recycled content
- Timber: 100% FSC-certified
- Regional sourcing: 40% within 500km

Scoring based on exceeding minimums:

- Meet all mandatory minimums: 8 points
- Exceed 2+ categories by 10%+: 12 points

- Exceed all categories by 15%+: 15 points
- Low-VOC materials compliance: included in Indoor Environmental Quality scoring

5.5 Indoor Environmental Quality Scoring (15 points maximum)

- Mandatory ventilation and acoustic standards met: 6 points baseline
- Operable windows >30% spaces: 2 points
- Thermal comfort monitoring: 2 points
- Enhanced daylighting (>75% spaces with natural light): 3 points
- Low-emitting materials certification: 2 points

5.6 Innovation and Design Process Scoring (10 points maximum)

- Exemplary performance in any category: 2 points each (max 6 points)
- Innovative sustainability features not addressed in standard categories: 1 point each (max 4 points)
- Examples: Net Zero Energy, Carbon Positive design, Circular Economy features

5.7 Site Sustainability and Biodiversity Scoring (15 points maximum)

- Biodiversity baseline assessment completed: 3 points
- Zero net loss of biodiversity achieved: 5 points (mandatory for sites requiring assessment per POL-UD-002 Section 4.1)
- Tree preservation >60% mature trees: 3 points
- Native species landscaping >70%: 2 points
- Wildlife corridors and habitat creation: 2 points

6. SUSTAINABILITY ASSESSMENT PROCESS

STAGE 1: PRELIMINARY ASSESSMENT (CONCEPT DESIGN - 30% COMPLETION)

Timeline: Week 4-6 of design process

Responsible: Contractor's Sustainability Consultant (or equivalent) with Contractor's Lead Architect (or equivalent)

Actions:

1. Review concept design drawings and preliminary specifications
2. Complete Preliminary Sustainability Scorecard using methodology in Section 5
3. Identify gap between current design scoring and target certification level
4. Conduct energy modeling (preliminary) to validate energy performance tier
5. Review material selections against POL-UD-002 Section 2.4 requirements
6. Assess renewable energy feasibility and integration options
7. Prepare Preliminary Assessment Report Form PAR-11

Deliverables:

- Preliminary Sustainability Scorecard (projected points: XX/100)
- Energy model results (preliminary)
- Gap analysis: current score vs. target
- Recommendation report for design optimization
- Form PAR-11 with risk flagging

Gateway Review: Contractor's Assistant Project Director (or equivalent) review within 5 business days. Proceed to Stage 2 only if projected score is within 5 points of target OR action plan approved to close gap.

STAGE 2: DETAILED ASSESSMENT (DEVELOPED DESIGN - 60% COMPLETION)

Timeline: Week 12-15 of design process

Responsible: Sustainability Consultant with full design team

Actions:

1. Review detailed design drawings, specifications, and calculations
2. Update Sustainability Scorecard with refined analysis
3. Conduct detailed energy modeling with final HVAC systems and façade design
4. Verify material certifications and supply chain compliance
5. Calculate renewable energy system capacity and annual generation

6. Review biodiversity assessment and landscape design (if applicable)
7. Assess water efficiency features and calculate consumption
8. Prepare Detailed Sustainability Assessment Report Form DSAR-16
- 9. Reference POL-UD-002 Section 2 to confirm all mandatory minimums achieved**
10. Flag any potential non-compliance or exception requirements

Deliverables:

- Detailed Sustainability Scorecard (revised projected points)
- Energy model report with annual consumption analysis
- Water balance calculations
- Material certifications register
- Renewable energy system specifications and generation projections
- Biodiversity assessment update
- Form DSAR-16 with compliance confirmation
- **Exception requests (if required) per POL-UD-002 Section 8**

Gateway Review: Contractor's Assistant Project Director (or equivalent) + HCSA's Project Manager joint review. Requires formal approval to proceed to certification submission. Any exceptions must be processed per POL-UD-002 Section 8.2 before proceeding.

STAGE 3: PRE-CERTIFICATION SUBMISSION (100% DESIGN DOCUMENTATION)

Timeline: Week 22-24 (immediately pre-tender)

Responsible: Sustainability Consultant

Actions:

1. Finalize all sustainability documentation for certification body
2. Complete certification application forms per chosen scheme
3. Compile design documentation: drawings, specifications, calculations, reports

4. Prepare certification submission package per third-party requirements
5. Conduct internal quality review of submission completeness
6. Obtain Contractor's Assistant Project Director (or equivalent) sign-off on certification submission
7. Submit Preliminary/Design Stage Certification application
8. Pay certification body fees (typically \$15,000-\$50,000 depending on project size)

Deliverables:

- Complete certification submission package
- Preliminary/Design Stage Certification application
- Payment confirmation
- Submission acknowledgment from certification body
- Updated project schedule with certification review timeline (typically 4-6 weeks)

Hold Point: Await certification body preliminary review and feedback before construction commencement.

STAGE 4: CONSTRUCTION PHASE MONITORING

Timeline: Throughout construction period

Responsible: Sustainability Consultant with Contractor's Project Manager (or equivalent)

Monthly actions:

1. Site inspection to verify sustainability measures implementation
2. Review material delivery certifications (recycled content, FSC, etc.)
3. Monitor construction waste diversion and recycling rates (target 70% per POL-UD-002)
4. Track water and energy consumption during construction
5. Photograph sustainability features as installed
6. Document any design changes impacting sustainability scoring

7. Prepare Monthly Sustainability Report Form MSR-20

Quarterly actions:

1. Conduct formal sustainability compliance audit
2. Update Sustainability Scorecard if design changes occurred
3. Report to HCSA's Project Manager on portfolio sustainability status
4. Review deviation log and initiate corrective actions

Pre-completion actions (4 weeks before practical completion):

1. Commission Building Management System and verify operational functionality
2. Conduct pre-completion sustainability inspection with certification body
3. Compile as-built documentation for final certification
4. Prepare commissioning reports for all sustainability-critical systems
5. Train building operators on sustainability features and monitoring requirements

Deliverables:

- Monthly Sustainability Report Form MSR-20 (12+ reports during typical project)
- Quarterly compliance audit reports
- Material certification register (ongoing)
- Construction waste diversion documentation
- Pre-completion inspection report
- As-built sustainability documentation package

STAGE 5: FINAL CERTIFICATION AND POST-OCCUPANCY

Timeline: Months 1-12 post-occupancy

Responsible: Sustainability Consultant with building management team

Actions:

1. Monitor actual building performance: energy, water, waste, occupant satisfaction
2. Collect 12 months of utility data for performance verification

3. Conduct occupant surveys on indoor environmental quality (minimum 50% response rate)
4. Commission third-party verification of sustainability performance
5. Compile Final Certification submission package
6. Address any certification body queries or requests for additional documentation
7. Obtain Final Certification award
8. Prepare Post-Occupancy Sustainability Performance Report Form SPR-25

Performance verification requirements:

- Energy consumption within 10% of modeled prediction (or provide justification)
- Water consumption meets efficiency targets
- Waste diversion rates maintained in operational phase
- Occupant satisfaction scores >75% for thermal comfort, air quality, lighting

Deliverables:

- 12-month utility consumption data
- Occupant satisfaction survey results
- Third-party verification report
- Final Certification award certificate
- Form SPR-25: Sustainability Performance Report
- Lessons learned document for future projects

Celebration: Certification achievement announced in company communications, project team recognition, marketing collateral development.

7. THIRD-PARTY CERTIFICATION COORDINATION

7.1 Certification Body Engagement

Registration timing: Within 30 days of design commencement per POL-UD-002 Section 5.3

Engagement process:

1. Submit project registration to selected certification body
2. Pay registration fee (typically \$2,000-\$5,000)
3. Assign certification ID and primary contact
4. Receive certification scheme guidance and templates
5. Schedule preliminary consultation with certification assessor

7.2 Certification Review Stages

Stage 1: Design Review (preliminary certification)

- Submission at 100% design documentation
- Review period: 4-6 weeks
- Outcome: Preliminary certification award OR feedback for revisions
- Typical revisions: 1-2 rounds, 2 weeks per round

Stage 2: Construction Review

- Submission of as-built documentation and commissioning reports
- Site inspection by certification assessor
- Review period: 4-6 weeks
- Outcome: Provisional certification OR outstanding items list

Stage 3: Final Certification

- Submission of 12-month operational data
- Performance verification report
- Review period: 4-8 weeks
- Outcome: Final certification award at achieved level

7.3 Certification Cost Budget

Typical cost allocation (percentage of total sustainability budget):

- Certification body fees: 15-20%
- Sustainability Consultant fees: 40-50%
- Third-party verification and testing: 10-15%
- Enhanced sustainability features (design/construction): 20-30%

- Commissioning and performance monitoring: 5-10%

Benchmark: Total sustainability budget typically 3-8% of total project construction cost, varying by target certification level and baseline code requirements.

8. DEVIATION APPROVAL WORKFLOW

8.1 Deviation Categories and Thresholds

Category A: Minor Deviations (Sustainability Consultant approval)

- Single sustainability feature modification
- <5 point impact on certification scorecard
- No impact on mandatory minimums per POL-UD-002 Section 2
- Alternative measure provides equivalent benefit
- Examples: substitute material with equivalent recycled content, alternative renewable energy technology

Category B: Moderate Deviations (Project Director approval)

- Multiple feature modifications OR 5-10 point certification impact
- Does not breach mandatory policy minimums
- Requires cost-benefit analysis or technical justification
- Examples: reduced renewable energy capacity within policy minimums, alternative water efficiency approach

Category C: Major Deviations (Exception Request required)

- Breach of mandatory minimums in POL-UD-002 Section 2
- 10 point certification impact OR risk to target certification level
- Requires formal Exception Request per POL-UD-002 Section 8
- Examples: inability to meet 20% renewable energy requirement, failure to achieve minimum certification level

8.2 Deviation Request Process (Category A & B)

Process for deviations NOT requiring policy exception:

Step 1: Deviation Identification (Day 1)

- Contractor's project team member (or equivalent) identifies sustainability deviation requirement
- Document reason: cost, technical constraint, schedule, client requirement
- Assess impact on certification scorecard using Section 5 methodology
- Determine deviation category per Section 8.1

Step 2: Technical Assessment (Days 2-5)

- Sustainability Consultant evaluates deviation impact
- Proposes alternative compliance measures if possible
- Calculates revised sustainability scorecard
- Prepares Deviation Request Form DR-13

Step 3: Cost-Benefit Analysis (Days 6-10)

- Quantity Surveyor assesses cost differential
- Compare original specification vs. proposed deviation
- Calculate lifecycle cost implications (if relevant)
- Prepare cost impact summary

Step 4: Approval Routing (Days 11-15)

- **Category A:** Sustainability Consultant approval via Form DR-13
- **Category B:** Contractor's Assistant Project Director (or equivalent) approves with Sustainability Consultant's recommendation
- Document approval in Deviation Log (maintained in project repository)
- Communicate decision to design team and update specifications

Step 5: Scorecard Update (Days 16-20)

- Revise Sustainability Scorecard with approved deviation

- Verify target certification level still achievable
- Flag risk if buffer margin reduced below 5 points
- Update Monthly Sustainability Report

Timeline: Maximum 20 business days from deviation identification to resolution.

8.3 Major Deviation Process (Category C - Exception Required)

When deviation breaches POL-UD-002 mandatory minimums:

This process creates a gray area compared to POL-UD-002 Section 8.2 exception process:

Key differences between this SOP and POL-UD-002:

1. Approval authority:

- POL-UD-002 Section 8.2: Minor exceptions = Contractor's Construction Management Director (or equivalent) + Contractor's Assistant Project Director (or equivalent)
- This SOP Section 8.3: Contractor's Assistant Project Director (or equivalent) initiates, but must follow POL-UD-002 approval authorities

2. Timeline:

- POL-UD-002 Section 8.2: 25 days maximum for approval decision
- This SOP Section 8.3: Allows up to 30 days for complete process including implementation

3. Alternative measures:

- POL-UD-002 Section 8.2: Requires "alternative compliance measures or mitigation"
- This SOP Section 8.3: Suggests "compensatory sustainability enhancements" may be proposed but doesn't mandate them

SOP-UD-002 Deviation Process (integrates with but differs slightly from policy):

Step 1: Exception Necessity Determination (Days 1-3)

- Contractor's Assistant Project Director (or equivalent) confirms deviation cannot be resolved through Category A/B process

- Document which POL-UD-002 Section 2 mandatory minimum(s) affected
- Convene emergency review: Contractor's Assistant Project Director (or equivalent), Sustainability Consultant, Contractor's Lead Architect (or equivalent), Contractor's Cost Consultant (or equivalent)
- Explore all alternatives before proceeding with exception request

Step 2: Exception Request Preparation (Days 4-10)

- Complete Exception Request Form EX-04 (referenced in POL-UD-002 Section 8.2)
- Provide detailed technical justification and supporting evidence
- **Propose compensatory sustainability enhancements** (this SOP suggests but doesn't mandate, whereas POL-UD-002 requires alternative measures)
- Quantify impacts: cost, schedule, certification scoring, environmental performance
- Prepare risk assessment if exception granted

Step 3: HCSA's Project Manager Review (Days 11-20)

- Technical review of exception justification
- May commission independent expert review (adds 5-10 days)
- **Reference POL-UD-002 Section 8.1 to verify grounds for exception are valid**
- Prepare recommendation with conditions
- Flag to Contractor's Assistant Project Director (or equivalent) if compensatory measures are insufficient

Step 4: Approval per POL-UD-002 Authority Matrix (Days 21-30)

- Route to appropriate approval authority per POL-UD-002 Section 8.2:
 - Minor exceptions: HCSA's Project Manager
 - Moderate exceptions: Contractor's CEO (or equivalent)
 - Major exceptions: HCSA's Development Projects Director
- Note: Timeline may extend beyond 30 days for Board-level approvals requiring meeting scheduling
- Obtain documented approval with conditions

Step 5: Implementation and Monitoring (Post-Approval)

- Document approved exception in Exceptions Register
- Update Sustainability Scorecard and certification submission
- Implement compensatory measures (if approved)
- Enhanced monitoring per exception conditions
- Quarterly reporting to Chief Sustainability Officer

CRITICAL NOTE FOR PROJECT TEAMS: When a deviation requires an exception per this section, teams **MUST** follow POL-UD-002 Section 8.2 approval authorities and timelines. This SOP provides operational guidance but policy authority takes precedence. In case of any conflict between this SOP timeline (30 days) and policy timeline (25 days for approval), the policy timeline governs.

9. MONTHLY SUSTAINABILITY PERFORMANCE REPORTING

9.1 Monthly Report Requirements

Report due: 5th business day of each month covering previous month's activities

Mandatory content (Form MSR-20):

1. **Executive Summary:** One-page project status, key achievements, issues
2. **Certification Scorecard Status:** Current projected points vs. target
3. **Compliance Status:** Confirmation of ongoing compliance with POL-UD-002 mandatory minimums
4. **Key Performance Indicators:**
 - a. Energy performance tracking (design phase: model iterations; construction phase: site consumption)
 - b. Water efficiency measures status
 - c. Materials certifications received vs. outstanding
 - d. Renewable energy system installation progress
 - e. Construction waste diversion rate (target 70%)
5. **Issues and Risks:** Any emerging non-compliance risks or deviation requirements

6. **Upcoming Milestones:** Next 30-day sustainability deliverables and approvals
7. **Photos:** Sustainability features under construction (minimum 5 photos)

9.2 Report Distribution

- Contractor's Assistant Project Director (or equivalent) (primary recipient)
- Contractor's Construction Management Director (or equivalent)
- Contractor's CEO (or equivalent)
- Contractor's Compliance Officer (or equivalent) (for compliance tracking)
- HCSA's Project Manager
- Project file archive

9.3 Escalation Triggers

Immediate escalation required if:

- Projected certification score falls >5 points below target
- Mandatory minimum breach identified
- Cost overrun >10% on sustainability budget
- Schedule delay >2 weeks on critical sustainability milestone
- Authority or certification body raises significant concerns

10. EXCEPTION REQUEST INTEGRATION WITH POLICY

10.1 Policy-SOP Alignment

This SOP operationalizes POL-UD-002 Section 8 exception process with additional procedural detail. In all cases of conflict, POL-UD-002 requirements supersede this SOP.

Clear alignment:

- Exception grounds (POL-UD-002 Section 8.1) = applicable
- Exception form (Form EX-04) = same form used
- Approval authorities (POL-UD-002 Section 8.2) = govern all exceptions
- Documentation requirements = consistent

10.2 Pre-Exception Checklist

Before submitting exception request, Project Director must confirm:

- ☐ All Category A and B deviation alternatives exhausted
- ☐ Cost-benefit analysis completed with detailed financial modeling
- ☐ Client consultation completed (if applicable)
- ☐ Alternative compliance measures identified and costed
- ☐ Impact on project viability documented
- ☐ **POL-UD-002 Section 8.1 grounds for exception clearly demonstrated**
- ☐ Legal review completed (for contractual implications)
- ☐ Certification body consulted on impact to certification (if applicable)

11. SUSTAINABILITY CONSULTANT PERFORMANCE EVALUATION

11.1 Evaluation Criteria

At project completion, Contractor's Project Manager evaluates Sustainability Consultant performance:

Technical competency (30%):

- Accuracy of sustainability scoring and modeling
- Quality of design optimization recommendations
- Certification coordination effectiveness

Communication and collaboration (25%):

- Responsiveness to project team queries
- Quality of reporting and documentation
- Integration with design team workflow

Project outcomes (35%):

- Achievement of target certification level
- Actual building performance vs. predictions (post-occupancy)
- Budget and schedule adherence for sustainability scope

Innovation and value-add (10%):

- Identification of cost-effective sustainability solutions
- Contribution to enhanced project sustainability outcomes
- Knowledge transfer to internal team

11.2 Performance Rating Scale

- Exceptional (90-100%): Preferred consultant for future projects, fast-track procurement
- Satisfactory (70-89%): Eligible for future project consideration
- Needs Improvement (50-69%): Probationary status, enhanced oversight required for future engagement
- Unsatisfactory (<50%): Not eligible for future appointments

Performance ratings logged in Vendor Management System and influence future consultant selection.

12. CONTINUOUS IMPROVEMENT AND LESSONS LEARNED

12.1 Post-Project Review

Within 60 days of final certification award:

- Conduct lessons learned workshop with full project team
- Document what worked well and improvement opportunities
- Identify any policy or SOP updates needed
- Capture innovative approaches for knowledge sharing
- Complete Lessons Learned Form LL-28

12.2 Knowledge Management

- Best practices documented in Sustainability Knowledge Base
- Innovative details added to standard detail library
- Case studies prepared for internal training

- External publication opportunities identified (awards, conferences, journals)

12.3 SOP Updates

- Annual review by Chief Sustainability Officer
- Incorporate lessons learned from completed projects
- Update based on certification scheme revisions
- Align with policy updates (POL-UD-002 revisions)
- Technology and methodology updates

13. FORMS AND TEMPLATES REFERENCE

Form Code	Form Name	Purpose	Completed By
WR-09	Workshop Report Form	Pre-design sustainability workshop outcomes	Sustainability Consultant
PAR-11	Preliminary Assessment Report	Concept design sustainability scoring	Sustainability Consultant
DR-13	Deviation Request Form	Category A/B deviation approvals	Sustainability Consultant
DSAR-16	Detailed Sustainability Assessment Report	60% design sustainability assessment	Sustainability Consultant
MSR-20	Monthly Sustainability Report	Monthly performance reporting	Sustainability Consultant
SPR-25	Sustainability Performance Report	Post-occupancy performance verification	Sustainability Consultant

EX-04	Exception Request Form	Policy exception requests (shared with POL-UD-002)	HCSA's Development Projects Director
LL-28	Lessons Learned Form	Post-project review documentation	HCSA's Development Projects Director
BA-07	Biodiversity Assessment Form	Ecological site assessment (referenced from POL-UD-002)	Environmental Consultant

14. KEY PERFORMANCE INDICATORS

14.1 Process KPIs

- **Certification Success Rate:** Target >95% of projects achieve target certification level or higher
- **Timeline Compliance:** Target >90% of certification milestones met on schedule
- **Budget Adherence:** Target sustainability costs within $\pm 10\%$ of budget
- **First-Time Certification:** Target >80% of projects achieve certification on first submission (no major revisions)

14.2 Performance KPIs

- **Energy Performance:** Target >85% of projects meet or exceed modeled energy performance in first year
- **Exception Rate:** Target <10% of projects require exceptions to POL-UD-002 mandatory minimums
- **Occupant Satisfaction:** Target >80% occupant satisfaction scores for certified buildings

14.3 Reporting

- Monthly KPI dashboard to Chief Sustainability Officer
- Quarterly portfolio sustainability report to Executive Committee
- Annual sustainability performance report (public document)

Document Control:

Last Updated: 15 January 2026

Change Log: Version 2.4 - Enhanced deviation workflow and clarified exception process integration with POL-UD-002

IMPORTANT NOTE: This SOP must be read in conjunction with POL-UD-002 Green Building & Sustainability Standards Policy. In all cases of conflict or ambiguity, POL-UD-002 requirements take precedence over this SOP.